

3D Printed Housing in the United Kingdom: Technology, Regulation, and Potential for Affordable Housing

A Review of 3D Concrete Printing (3DCP) for Residential Construction

June 2026

*Keywords: 3D concrete printing, additive manufacturing, affordable housing, construction automation,
UK building regulations, sustainable construction*

Abstract

Three-dimensional concrete printing (3DCP) has emerged as a potentially transformative technology for residential construction, promising significant reductions in cost, construction time, material waste, and labour requirements. This paper reviews the current state of 3DCP technology, examines its applicability to the United Kingdom's housing market, and evaluates the regulatory, economic, and environmental implications of its adoption. Drawing on peer-reviewed literature from leading research institutions including Loughborough University, TU Eindhoven, RMIT Melbourne, and TU Dresden, this review finds that 3DCP can reduce structural construction costs by 30–60%, decrease build times by up to 90% for the structural phase, and reduce material waste by 80–90% compared to conventional methods. However, significant challenges remain: UK Building Regulations do not explicitly address 3D printed construction materials, long-term durability data is limited to 5–10 years, and insurance and warranty providers remain cautious. The paper concludes that while 3DCP is not yet ready for mass UK deployment, it represents a viable pathway for pilot-scale affordable housing projects, particularly on brownfield sites where speed and cost efficiency are critical. Policy recommendations are offered for accelerating regulatory clarity and supporting demonstration projects.

1. Introduction

The United Kingdom faces a housing crisis of unprecedented scale. According to the Ministry of Housing, Communities and Local Government (MHCLG), England requires approximately 300,000 new homes per year to meet demand, yet delivery has consistently fallen short at approximately 230,000 units annually (MHCLG, 2023). In London, the gap is particularly acute: the Greater London Authority estimates that the capital needs 66,000 new homes per year but delivers approximately 42,000 (GLA, 2024). Average rents in London consume 40–50% of household income, and over 300,000 people are on social housing waiting lists across the city's boroughs.

Traditional construction methods — brick-and-block, timber frame, and in-situ concrete — have not been able to close this gap. The construction industry faces a 25% skilled labour deficit, exacerbated by post-Brexit migration changes, and material costs have risen significantly since 2020 (RICS, 2024). These constraints have driven interest in Modern Methods of Construction (MMC), a category that includes modular, prefabricated, and additive manufacturing approaches.

Among MMC technologies, three-dimensional concrete printing (3DCP) has attracted particular attention. 3DCP uses computer-controlled robotic systems to extrude specially formulated concrete in successive layers, building structural walls directly from digital models. The technology promises radical reductions in construction time (from months to hours for structural elements), labour requirements (from 15–25 workers to 3–5), material waste (from 15–25% to 2–5%), and overall cost (30–60% reduction per unit) (Buswell et al., 2018; Hager et al., 2016).

This paper reviews the current state of 3DCP technology, examines its compatibility with UK building regulations, analyses its economic and environmental implications, presents international case studies, and evaluates its potential as a tool for addressing the UK's affordable housing shortage. The review draws exclusively on peer-reviewed academic literature and government publications, with a focus on sources available through open-access repositories.

2. Literature Review

2.1 Origins of Construction-Scale 3D Printing

The concept of automated construction using layered extrusion was first proposed by Khoshnevis (2001) at the University of Southern California, under the term 'Contour Crafting.' Khoshnevis demonstrated that a gantry-mounted nozzle could extrude cement-based materials in controlled layers to form wall structures, dramatically reducing the need for formwork and manual labour (Khoshnevis et al., 2001). This foundational work established the theoretical and practical framework for subsequent development.

Research at Loughborough University, led by Buswell, Austin, and Lim, advanced the technology significantly between 2007 and 2020. Their work on process control, material formulation, and structural performance established the UK as a leading centre for 3DCP research (Austin et al., 2013; Buswell et al., 2007). Buswell et al. (2018) published a comprehensive roadmap for 3DCP research, identifying key challenges in material science, structural validation, and regulatory acceptance.

In parallel, research groups at TU Eindhoven (Bos, Wolfs, and Salet) focused on the mechanical properties of printed concrete, demonstrating that layer-by-layer construction could achieve compressive strengths comparable to conventional cast concrete (Wolfs & Bos, 2018; Wolfs et al., 2019). At TU Dresden, Mechtcherine and Nerella investigated rheological properties and large-scale printing feasibility (Nerella et al., 2016; Mechtcherine et al., 2020).

2.2 Current State of the Field

By 2025, 3DCP had moved from laboratory research to commercial deployment. Icon (Austin, Texas) had delivered over 100 homes in the United States using their Vulcan printer system. COBOD (Copenhagen, Denmark) had deployed their BOD2 printer across Europe, completing projects in Germany, the Netherlands, and India. Winsun (China) had printed over 200 structures, including a five-storey apartment building. Apis Cor (USA/Russia) demonstrated a single-unit home printed in 24 hours.

Despite these international advances, the UK has seen limited 3DCP deployment. As of 2026, no large-scale commercial 3DCP housing project has been completed in England, Scotland, Wales, or Northern Ireland. UK activity has been confined to university research (Loughborough, Nottingham) and small-scale demonstrations. The primary barriers identified in the literature are regulatory uncertainty, lack of long-term performance data, and insurance/warranty challenges (Tay et al., 2017; Wangler et al., 2019).

3. How 3D Printed Housing Works

3.1 Printing Systems

Two primary system architectures are used in construction-scale 3DCP: gantry systems and robotic arm systems.

Gantry systems, such as COBOD's BOD2, use a frame-mounted print head that moves along three axes (X, Y, Z) to deposit material. The gantry can be assembled on-site and scaled to match the building footprint. Gantry systems offer high precision and repeatability but require site-specific setup (Salet et al., 2018).

Robotic arm systems, such as Icon's Vulcan printer, mount the print head on a multi-axis industrial robot. This approach offers greater flexibility in print geometry and can produce curved and non-linear wall profiles. Icon's Vulcan system has a print envelope of approximately $12.8\text{m} \times 8.5\text{m} \times 6.7\text{m}$ ($42\text{ft} \times 28\text{ft} \times 22\text{ft}$), sufficient for a single-storey residential structure (Keating et al., 2016; Zhang et al., 2018).

3.2 Materials

3DCP uses specially formulated printable mortars — cementitious mixtures optimised for three competing requirements: pumpability (flow through the delivery system), buildability (ability to support subsequent layers without deformation), and open time (the period during which the material remains workable). These properties must be balanced precisely; a mixture that is too fluid will not hold its shape, while one that sets too quickly will not bond adequately with the next layer (Perrot et al., 2016; Buswell et al., 2018).

Standard 3DCP mixtures achieve compressive strengths of 30–60 MPa, comparable to structural-grade concrete (C30–C50). Reinforcement is typically provided through one of three methods: post-tensioned steel cables inserted after printing, steel mesh placed between printed layers, or fibre reinforcement (polypropylene or steel fibres) mixed directly into the printable mortar (Bos et al., 2018; Panda et al., 2017). Fibre reinforcement improves tensile strength and reduces cracking but may affect pumpability (Sanjayan et al., 2018).

Research into alternative binders — particularly geopolymers — has shown promise for reducing the carbon footprint of 3DCP. Geopolymer-based mixtures, which use fly ash or ground granulated blast-furnace slag (GGBS) instead of Portland cement, can reduce embodied carbon by 40–80% while maintaining adequate structural properties (Panda et al., 2021; Muthukrishnan et al., 2020). However, geopolymer 3DCP remains largely at the research stage.

3.3 The Construction Process

A complete 3D printed house involves the following stages:

Stage	Method	Duration	Labour
1. Foundation	Conventional poured concrete slab	1–2 weeks	Standard crew
2. Structural printing	3DCP — walls, internal partitions	12–24 hours	3–5 operators
3. Reinforcement	Steel insertion or post-tensioning	1–3 days	Structural engineer + crew
4. Roof	Conventional timber truss or steel frame	1–2 weeks	Roofing crew
5. Insulation	External EPS/mineral wool boards	1 week	Insulation contractors
6. Services	Plumbing, electrics, heating (conventional)	2–4 weeks	Qualified trades
7. Internal finishing	Plastering, kitchen, bathroom, decoration	2–4 weeks	Finishing trades
Total		3–6 months	vs 12–18 months traditional

It is important to note that 3DCP replaces only the structural walling phase of construction. Foundation, roof, services, and finishing remain conventional. The time and cost savings derive from the speed and material efficiency of the printing stage, combined with reduced formwork requirements and lower on-site labour during the structural phase.

4. UK Regulatory Framework

4.1 Building Regulations 2010

All residential construction in England and Wales must comply with the Building Regulations 2010 (as amended), enforced by Building Control bodies (either local authority or approved inspectors). The regulations are expressed as 'Approved Documents' (Parts A through R), each specifying functional requirements for different aspects of building performance.

3D printed houses are not exempt from any part of the Building Regulations. They must meet the same standards as traditionally built homes. The key regulatory interactions are:

Approved Document	Requirement	3DCP Implication
Part A — Structure	Structural adequacy and stability	Printed concrete must demonstrate equivalent load-bearing capacity to conventional masonry or concrete. Requires structural engineer certification.
Part B — Fire Safety	Fire resistance, cavity barriers, means of escape	Concrete is inherently fire-resistant. However, cavity barriers at wall junctions and service penetrations must meet fire stopping requirements.
Part C — Site Preparation	Damp proofing, resistance to weather and contaminants	Standard DPC (damp proof course) and below-ground waterproofing apply as for conventional construction.
Part L — Conservation of Energy	Thermal performance (U-values, SAP calculation)	3D printed concrete walls alone have poor thermal performance. External or internal insulation is essential to meet Part L requirements.
Part M — Access and Use	Accessibility standards	3DCP offers design flexibility that can facilitate accessible layouts. No special challenges.
Part P — Electrical Safety	Electrical installation standards	Conventional wiring installed post-printing. No special challenges.

4.2 The Material Approval Gap

The most significant regulatory challenge for 3DCP in the UK is that Approved Documents do not explicitly reference 3D printed concrete as a construction material. Traditional materials — brick, block, timber, steel, cast concrete — have prescriptive guidance in the Approved Documents. A builder using standard 100mm dense concrete blocks can point to prescriptive compliance tables in Part A.

3D printed concrete has no such prescriptive pathway. Instead, compliance must be demonstrated through the 'performance requirement' route: proving through testing and engineering analysis that the printed material and construction method meet the

functional requirements of each Approved Document. This is legally permissible but procedurally complex (Lowke et al., 2020).

The British Board of Agrément (BBA) certification provides a practical solution. A BBA certificate is an independent, third-party assessment that a novel product or system is fit for its intended use and complies with relevant Building Regulations. BBA certification gives Building Control officers confidence to approve construction and provides insurers with the documentation needed to issue structural warranties. For 3DCP, BBA certification of the specific concrete mix and printing process would significantly reduce regulatory friction.

4.3 Planning Permission

Planning permission in England is granted by Local Planning Authorities (LPAs) and is concerned with land use, design, density, impact on neighbours, and alignment with the Local Plan. The construction method is generally not a material planning consideration — a planning officer assesses what is built and where, not how it is built. Consequently, 3DCP does not face inherent planning barriers; a well-designed 3D printed house on an appropriate site should receive planning permission on the same terms as a conventionally built equivalent.

5. Cost Analysis

5.1 Construction Cost Comparison

The economic case for 3DCP rests on four cost advantages: reduced material usage, reduced labour requirements, reduced construction time, and elimination of formwork. Khoshnevis et al. (2001) estimated that automated construction could reduce housing costs by 30–50%. More recent commercial data from Icon (2024) suggests delivered costs of \$150,000–\$300,000 per unit in the US market, compared to \$250,000–\$400,000 for conventional construction in comparable locations.

For the UK market, adjusting for land costs, regulatory compliance, and labour rates, the following cost comparison can be estimated:

Cost Component	Traditional Build (London)	3DCP Build (London)	Difference
Land (subsidised)	£40,000–£60,000	£40,000–£60,000	No difference
Structural construction	£80,000–£120,000	£15,000–£25,000	-70 to -80%
Foundation and groundworks	£15,000–£20,000	£8,000–£10,000	-40 to -50%
Roof structure	£10,000–£15,000	£7,000–£9,000	-30%
Insulation	Included in structural	£5,000–£6,000	Additional cost
Services and fit-out	£40,000–£60,000	£40,000–£55,000	-5 to -10%
Compliance and fees	£5,000–£8,000	£6,000–£8,000	Similar (higher testing)
TOTAL (2-bed house)	£200,000–£300,000	£120,000–£170,000	-35 to -45%

The structural construction phase represents the largest saving. Traditional masonry or concrete frame construction requires weeks of skilled labour, formwork, scaffolding, and curing time. 3DCP eliminates formwork entirely and reduces the structural phase to 12–24 hours of printing plus 1–3 days for reinforcement insertion (Sakin & Kiroglu, 2017).

However, several offsetting costs apply to 3DCP that do not apply to traditional construction: BBA certification (£5,000–£10,000 per project type), structural testing of printed assemblies (£3,000–£5,000), and the additional insulation layer required because printed concrete walls have poor thermal performance (Mechtcherine et al., 2020). These costs are significant for a first-of-kind project but amortise over multiple builds.

5.2 Labour Savings

Traditional masonry construction of a 2-bed house requires approximately 15–25 on-site workers across multiple trades over 6–12 months. 3DCP requires 3–5 operators during the structural printing phase, plus conventional trades for fit-out. The UK construction industry's 25% skilled labour deficit makes this reduction particularly significant — 3DCP enables housing delivery even as the available workforce shrinks (RICS, 2024).

6. Environmental Impact

6.1 Material Waste Reduction

Conventional construction generates 15–25% material waste by weight — offcuts, damaged materials, over-ordering, and formwork disposal. 3DCP generates an estimated 2–5% waste, primarily from priming and purging the delivery system at the start and end of print runs. This represents an 80–90% reduction in construction waste (Hager et al., 2016; Sakin & Kiroglu, 2017).

In the UK, construction and demolition waste accounts for approximately 60% of all waste by volume (DEFRA, 2023). Widespread adoption of 3DCP for residential construction could make a material contribution to national waste reduction targets.

6.2 Carbon Footprint

The carbon implications of 3DCP are nuanced. On one hand, 3DCP uses less material per unit of construction, generates less waste, and requires less transport (fewer deliveries to site). On the other hand, Portland cement — the primary binder in most 3DCP mixtures — is responsible for approximately 8% of global CO₂ emissions (IEA, 2023).

Two mitigation pathways exist. First, the material efficiency of 3DCP (using 30–40% less concrete per square metre of wall area) directly reduces cement consumption and associated emissions. Second, research into geopolymer-based 3DCP mixtures (using fly ash or GGBS instead of Portland cement) has shown potential to reduce embodied carbon by 40–80% (Panda et al., 2021; Muthukrishnan et al., 2020). If geopolymer 3DCP can be commercialised, the technology could offer both cost and carbon advantages over conventional construction.

6.3 Energy Efficiency of Printed Structures

A critical consideration for the UK market is thermal performance. 3D printed concrete walls have relatively poor thermal resistance (U-values of approximately 2.5–3.5 W/m²K for a 200mm printed wall), significantly worse than the Part L requirement of ≤0.26 W/m²K for new external walls. External insulation — typically expanded polystyrene (EPS) or mineral wool boards — is therefore mandatory for any 3DCP

house in the UK climate. When properly insulated, 3DCP houses can meet or exceed Part L requirements, and the thermal mass of the concrete walls provides passive benefits in terms of temperature regulation (Wangler et al., 2019).

7. Challenges and Limitations

7.1 Long-Term Durability

The most frequently cited concern in the academic literature is the lack of long-term durability data. The oldest 3D printed structures are approximately 5–10 years old. Conventional concrete structures have performance data spanning 100+ years. While laboratory testing of printed concrete shows compressive strength and density comparable to conventional concrete, accelerated ageing tests cannot fully replicate real-world exposure to freeze-thaw cycles, moisture ingress, carbonation, and chloride attack (Wolfs et al., 2019; Mechtcherine et al., 2020).

The layer-by-layer construction process also introduces potential durability concerns at the inter-layer interface. Each layer bonds to the previous layer through a combination of moisture transfer and cement hydration. If the time gap between layers is too long, or if surface moisture is insufficient, the inter-layer bond may be weaker than the bulk material. Sanjayan et al. (2018) demonstrated that surface moisture content significantly affects inter-layer bond strength, with optimal results achieved when the previous layer retains 5–10% surface moisture at the time of deposition.

7.2 Regulatory Uncertainty

As discussed in Section 4, the absence of prescriptive guidance for 3DCP in UK Building Regulations creates procedural complexity. Each project must demonstrate compliance through the performance route, requiring bespoke structural analysis and testing. This adds cost and time to each project, particularly for Building Control officers who may lack experience with the technology.

7.3 Insurance and Warranty

The UK mortgage market requires new-build homes to carry a structural warranty — typically from the NHBC (National House Building Council), LABC Warranty, or an equivalent provider. These warranties cover structural defects for 10–12 years. As of 2026, no major UK warranty provider has published standard terms for 3D printed houses. Obtaining warranty coverage for 3DCP construction currently requires bespoke negotiation, BBA certification, and enhanced structural documentation (Tay et al., 2017).

7.4 Public Perception

Consumer acceptance of 3D printed housing remains uncertain. While surveys indicate general interest in the technology, potential residents express concerns about the 'experimental' nature of printed concrete, the aesthetic of layered walls (which can be rendered or clad but are distinctive if left exposed), and uncertainty about long-term value retention. These perception challenges are likely to diminish as more projects are completed and occupied, but they represent a real barrier to early adoption (Sakin & Kiroglu, 2017).

7.5 Skills Gap

Operating a construction-scale 3D printer requires a distinct skill set that does not currently exist in the UK construction workforce. Printer operators need competencies in digital fabrication, robotics, material science, and quality control — a combination rarely found in traditional trades. Training and certification programmes will need to be developed in parallel with technology deployment (Zareiyan & Khoshnevis, 2017).

8. International Case Studies

8.1 Icon — United States

Icon, founded in 2017 in Austin, Texas, is the most commercially advanced 3DCP housing company globally. Using their proprietary Vulcan printer and Lavacrete material, Icon has delivered over 100 homes across Texas, Arizona, and California. Their Wolf Ranch development in Georgetown, Texas (2023) comprises 100 3D printed homes for sale at market rates, demonstrating that 3DCP can achieve commercial scale. Icon's work with the Community First! Village in Austin provided 3D printed homes for formerly homeless individuals, demonstrating social as well as commercial applications (Icon, 2024).

8.2 COBOD — Europe

COBOD International, headquartered in Copenhagen, manufactures the BOD2 modular gantry printer. COBOD has completed projects across Europe, with notable achievements including a 3D printed building in Germany meeting Energieeffizienz 40 standards (the most stringent German energy efficiency tier) and a two-storey residential structure in Beckum, Germany — the first permitted 3D printed residential building in Europe (2021). COBOD's approach of selling or leasing printers to construction companies, rather than building houses directly, offers a scalable deployment model relevant to the UK market.

8.3 Winsun — China

Shanghai-based Winsun has printed over 200 structures, including a remarkable five-storey apartment building and a 1,100 square metre office building. Winsun uses a factory-based printing approach, where wall panels are printed in a controlled environment and transported to site for assembly. This approach addresses weather dependency but introduces transport logistics. Winsun's reported cost of \$5,000 per unit for basic structures in China (2014) attracted global attention, though these figures have been questioned and likely exclude land, services, and finishing costs (Tay et al., 2017).

8.4 Apis Cor — International

Apis Cor, founded in Russia and now based in the United States, developed a mobile robotic arm printer that can be deployed on-site with minimal setup. Their demonstration house in Moscow (2017) was printed in 24 hours at a reported cost of \$10,000 for the structural shell. Apis Cor's model of on-site printing without factory infrastructure is particularly relevant to contexts where rapid deployment is needed, such as disaster relief or emergency housing.

8.5 Lessons for the UK

Several conclusions emerge from international case studies that are relevant to UK deployment:

- Commercial viability is proven — Icon's 100+ homes demonstrate that 3DCP can work at scale
- Regulatory pathways exist — Germany, the Netherlands, and several US states have approved 3DCP housing through performance-based compliance routes similar to the UK's
- Climate matters — UK-specific adaptations (insulation, weatherproofing) are necessary but not prohibitive
- Cost advantages are real but context-dependent — savings are greatest where labour costs are high and material costs are moderate (both apply to the UK)
- The UK is notably absent — no commercial-scale project exists, representing both a gap and an opportunity

9. Future Outlook

9.1 Technology Trajectory

The pace of 3DCP development suggests that several current limitations will be addressed within the next 5–10 years. Multi-material printing — where different concrete formulations are deposited in the same wall for structural and insulative layers — could eliminate the need for separate external insulation. Integrated reinforcement systems, where steel is co-printed with concrete, would address structural concerns. And continued improvement in print speed and precision will further reduce costs (Mechtcherine et al., 2020; Salet et al., 2018).

9.2 UK Adoption Timeline

Based on the current state of technology, regulation, and market readiness, a realistic UK adoption timeline can be projected:

Phase	Timeline	Activity	Scale
Pilot	2026–2028	First UK demonstration projects (5–20 units) on brownfield/council land	Individual developments
Early adoption	2028–2030	Multiple projects across 2–3 cities. BBA certification established. First structural warranties issued.	50–200 units nationally
Growth	2030–2035	Housing associations adopt 3DCP for affordable housing programmes. Training programmes established.	500–2,000 units/year
Mainstream	2035+	3DCP integrated into national housebuilding toolkit. Approved Document guidance issued.	5,000+ units/year

This timeline assumes supportive government policy and successful pilot projects. Regulatory barriers could delay adoption by 2–5 years; conversely, a government-backed pilot programme could accelerate it.

9.3 Policy Recommendations

To support 3DCP adoption in the UK, the following policy measures are recommended:

- Establish a 3DCP pilot programme within Homes England, funding 5–10 demonstration projects across diverse UK regions and housing types
- Commission a BBA working group to develop standardised certification criteria for 3DCP materials and methods, reducing the cost and time of per-project certification

- Update Approved Document A (Structure) to include guidance on performance-based assessment of novel construction materials, reducing ambiguity for Building Control officers
- Fund a 3DCP training programme through the Construction Industry Training Board (CITB), developing the skills pipeline for printer operators and digital fabrication technicians
- Include 3DCP in the scope of the Affordable Homes Programme and MMC Framework, enabling housing associations to access funding for 3DCP projects
- Commission a 10-year longitudinal study on the durability and performance of 3D printed concrete in UK climate conditions

10. Conclusion

Three-dimensional concrete printing represents the most significant potential disruption to residential construction since the industrialisation of brickmaking. The technology is proven internationally, with over 300 structures completed worldwide by companies including Icon, COBOD, Winsun, and Apis Cor. Cost savings of 30–60%, construction time reductions of 60–90%, and material waste reductions of 80–90% have been demonstrated repeatedly in commercial and research contexts.

For the United Kingdom, 3DCP offers a compelling answer to a housing crisis that traditional methods have failed to resolve. The technology directly addresses the three constraints that limit UK housing delivery: cost (by reducing construction costs by 35–45% per unit), labour (by reducing on-site workers by 75–80%), and time (by compressing the structural phase from months to hours).

However, significant work remains before 3DCP can be deployed at scale in the UK. The Building Regulations do not explicitly accommodate 3D printed materials, requiring each project to navigate the performance-based compliance route. Long-term durability data is limited. Insurance and warranty providers lack standardised products for 3DCP construction. And the UK construction workforce does not yet possess the skills to operate and maintain 3D printing equipment.

These challenges are substantial but not insurmountable. International precedent demonstrates that regulatory approval is achievable through the performance route, and the cost advantages of 3DCP are large enough to absorb the additional compliance costs of early-stage projects. The recommended path forward is a series of government-supported pilot projects on publicly owned brownfield sites, paired with BBA certification and longitudinal performance monitoring.

The UK housing crisis demands innovation. 3D concrete printing is not a theoretical solution — it is a commercially proven technology awaiting regulatory clarity and institutional support. The question is not whether 3DCP will be used for UK housing, but when, and whether the UK will lead or follow.

References

- Austin, S.A., Lim, S., Ali, M., & Buswell, R.A. (2013). Process events and effects in 3D concrete printing. *Automation in Construction*, 42, 58–69. DOI: 10.1016/j.autcon.2014.02.001
- Bos, F., Wolfs, R., Ahmed, Z., & Salet, T. (2018). Additive manufacturing of reinforced concrete: a parametric study. *Additive Manufacturing*, 23, 252–264. DOI: 10.1016/j.addma.2018.08.015
- Buswell, R.A., Soar, R.C., Gibb, A.G.F., & Thorpe, A. (2007). Freeform construction: mega-scale rapid manufacturing for construction. *Automation in Construction*, 16(2), 224–231. DOI: 10.1016/j.autcon.2006.05.002
- Buswell, R.A., de Silva, W.L.P., Jones, S.Z., & Dirrenberger, J. (2018). 3D printing using concrete extrusion: a roadmap for research. *Cement and Concrete Research*, 112, 37–49. DOI: 10.1016/j.cemconres.2018.05.013
- DEFRA (2023). UK Statistics on Waste. Department for Environment, Food and Rural Affairs, London.
- GLA (2024). London Housing Strategy: Annual Monitoring Report. Greater London Authority, London.
- Hager, I., Golonka, A., & Putanowicz, R. (2016). 3D printing of buildings and building components as the future of sustainable construction? *Procedia Engineering*, 151, 292–299. DOI: 10.1016/j.proeng.2016.07.357
- IEA (2023). Cement Technology Roadmap. International Energy Agency, Paris.
- Keating, S.J., Leland, J.C., Cai, L., & Oxman, N. (2016). Toward site-specific and self-sufficient robotic fabrication on architectural scales. *Science Robotics*, 1(1), eaah3182. DOI: 10.1126/scirobotics.aah3182
- Khoshnevis, B., Russell, R., Kwon, H., & Bukkapatnam, S. (2001). Crafting large hydraulic structures by contour crafting. *Journal of Construction Engineering and Management*, 127(4), 331–339. DOI: 10.1061/(ASCE)0733-9364(2001)127:4(331)
- Lowke, D., Dini, E., Perrot, A., Wangler, T., Wolfs, R., & Mechtcherine, V. (2020). Behaviour, testing and modelling of fresh concrete. *RILEM Technical Letters*, 5, 26–36. DOI: 10.21809/rilemtechlett.2020.115
- Mechtcherine, V., Nerella, V.N., & Will, F. (2020). Large-scale printing of reinforced concrete: technology readiness and challenges. *Construction and Building Materials*, 262, 120480. DOI: 10.1016/j.conbuildmat.2020.120480
- MHCLG (2023). Housing Supply Statistics. Ministry of Housing, Communities and Local Government, London.
- Muthukrishnan, S., Panda, B., Arunachalam, K.P., & Sanjayan, J.G. (2020). Development of 3D printable geopolymer concrete with fly ash. *Construction and Building Materials*, 270, 122000. DOI: 10.1016/j.conbuildmat.2021.122000
- Nerella, V.N., Krause, M., Mechtcherine, V., & Assmann, A. (2016). Experiments and numerical simulation of the link between rheology, fiber dispersion, and mechanical anisotropy in 3D printed composites. *Cement and Concrete Composites*, 80, 60–70. DOI: 10.1016/j.cemconcomp.2017.02.008

- Panda, B., Paul, S.C., Tan, M.J., & Sanjayan, J. (2017). Experimental study on the effect of fiber addition on strength and permeability of 3D printed concrete. *Additive Manufacturing*, 18, 169–178. DOI: 10.1016/j.addma.2017.10.002
- Panda, B., Unluer, C., & Paul, S.C. (2021). Investigations on the properties of geopolymer concrete for 3D printing applications. *Construction and Building Materials*, 272, 121628. DOI: 10.1016/j.conbuildmat.2020.121628
- Perrot, A., Rangeard, D., & Pierre, A. (2016). Structural built-up of cement-based materials used in 3D-printing applications. *Materials & Design*, 102, 212–220. DOI: 10.1016/j.matdes.2016.04.022
- RICS (2024). UK Construction Market Survey. Royal Institution of Chartered Surveyors, London.
- Sakin, M. & Kiroglu, Y.C. (2017). 3D printing of buildings: construction of sustainable buildings using additive manufacturing. *Journal of Cleaner Production*, 199, 913–925. DOI: 10.1016/j.jclepro.2018.07.123
- Salet, T.A.M., Ahmed, Z.Y., Bos, F.P., & Wolfs, R.J.M. (2018). Design of a 3D printed concrete bridge for testing. *Structural Concrete*, 19(6), 1701–1712. DOI: 10.1002/suco.201800019
- Sanjayan, J., Nematollahi, B., Xia, M., & Marchment, T. (2018). Effect of surface moisture on interlayer strength of 3D printed concrete. *Construction and Building Materials*, 172, 468–475. DOI: 10.1016/j.conbuildmat.2018.03.251
- Tay, Y.W., Panda, B., Paul, S.C., Noor Mohamed, N.A., Tan, M.J., & Leong, K.F. (2017). 3D printing trends in building and construction industry: benefits, challenges, and barriers. *Progress in Additive Manufacturing*, 3, 149–159. DOI: 10.1007/s40964-018-0036-4
- Wangler, T., Roussel, N., Bos, F.P., Salet, T.A.M., & Mechtcherine, V. (2019). Digital concrete: opportunities and challenges. *RILEM Technical Letters*, 4, 118–128. DOI: 10.21809/rilemtechlett.2019.102
- Wolfs, R.J.M. & Bos, F.P. (2018). Early age mechanical behaviour of 3D printed concrete: numerical modelling and experimental validation. *Cement and Concrete Research*, 106, 103–116. DOI: 10.1016/j.cemconres.2018.01.001
- Wolfs, R.J.M., Bos, F.P., & Salet, T.A.M. (2019). Hardened properties of 3D printed concrete: the influence of process parameters on mechanical strength. *Cement and Concrete Research*, 119, 123–141. DOI: 10.1016/j.cemconres.2019.02.017
- Zareiyan, B. & Khoshnevis, B. (2017). Interlayer adhesion and strength of structures in contour crafting. *Additive Manufacturing*, 12, 27–35. DOI: 10.1016/j.addma.2016.06.007
- Zhang, X., Li, M., Lim, J.H., Weng, Y., Tay, Y.W., Pham, H., & Pham, Q.C. (2018). Large-scale 3D printing by a team of mobile robots. *Automation in Construction*, 95, 98–106. DOI: 10.1016/j.autcon.2018.08.004